

### GENERAL NOTES

### 1. SEE SHEET L000 FOR PROJECT INFORMATION, SHEET INDEX, AND LEGEND.

- 2. SEE SHEET L001 FOR GENERAL NOTES.
- 4. ELECTRICAL CONTRACTOR, MECHANICAL CONTRACTOR, AND IRRIGATION CONTRACTOR TO COORDINATE WITH PAVING, CONCRETE, AND WALL CONTRACTORS ON SLEEVE LOCATIONS UNDER DRIVEWAYS, WALKS, AND
- 5. REFER TO SHEET L010 EXISTING CONDITIONS PLAN FOR BOUNDARY INFORMATION. ALL CONSTRUCTION STAKING MUST BE PERFORMED BY A
- 6. DO NOT SCALE THE DRAWINGS. WRITTEN DIMENSIONS ARE TO BE USED FOR ALL LAYOUT WORK.
- 7. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE LANDSCAPE ARCHITECT OF ANY LAYOUT DISCREPANCIES.
- 8. ALL SITE ELEMENTS SHALL BE STAKED IN THE FIELD AND APPROVED BY LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION.
- 9. AUTOCAD FILE AVAILABLE TO CONTRACTOR UPON REQUEST FOR FIELD

### **KEYNOTES**

- 1. EXISTING SIGNIFICANT TREE(S) TYP. SAVE AND PROTECT
- 2. EXISTING NEIGHBORING PROPERTY/SITE FEATURE
- 3. EXISTING CITY STREET/ALLEY SAVE AND PROTECT, REPAIR ANY DAMAGED
- AREAS PER CITY STANDARDS 4. EXISTING SHORELINE EDGE - SAVE AND PROTECT
- 5. LAKE MINNETONKA OHWL 929.40 SAVE AND PROTECT
- **6.** EXISTING 100 YEAR FLOODPLAIN LINE 931.50
- 7. SANITARY SEWER LINE SAVE AND PROTECT, V.I.F.
- 8. EXISTING WETLAND SAVE AND PROTECT
- 9. EXISTING RIP RAP SAVE AND PROTECT
- 10. EXISTING BEACH SAVE AND PROTECT

### SHEET NOTES

### 1. EXISTING BOATHOUSE TO BE REMOVED AND RECONSTRUCTED, REFER TO

- 3. PROPOSED SILT FENCE
- 4. PROPOSED DOUBLE ROW SILT FENCE
- 5. LIMITS OF DISTURBANCE
- 6. CONCRETE WASHOUT AREA, PER REGULATIONS
- 7. GRAVEL CONSTRUCTION ENTRANCE
- 8. PROPOSED TREE PROTECTION FENCE 9. PROPOSED BIO LOG EROSION CONTROL

### REMOVALS SCHEDULE

- **R2** EXISTING HOUSE TO BE REMOVED
- R3 EXISTING STRUCTURE TO BE REMOVED
- **R4** EXISTING PAVING TO BE REMOVED
- **R5** EXISTING STAIRS TO BE REMOVED
- **R6** EXISTING WALL TO BE REMOVED
- **R7** EXISTING LANDSCAPING TO BE REMOVED
- **R8** EXISTING FENCE TO BE REMOVED
- **R9** EXISTING STEPPERS TO BE REMOVED R10 EXISTING SITE ELEMENT TO BE REMOVED
- **R11** EXISTING UNDERGROUND UTILITY TO BE REMOVED
- R13 EXISTING WELL TO BE REMOVED

### TREE REMOVALS SCHEDILLE

IKEEKEMU	JVALS SUME	DULE				
KEY	SPECIES	DBH (IN.)	HEALTH	INSIDE 75' SETBACK	REPLACEMENT RATIO (INCHES)	
982	MAPLE	22.0	GOOD	Y	1:1, MIN 1.5" CAL.	
986	OAK	18.0	GOOD	Υ	1:1, MIN 1.5" CAL.	
1876	MAPLE	20.0	GOOD	Y	1:1, MIN 1.5" CAL.	
TOTAL INCHES 1	60					
TOTAL NUMBER OF DISEASED TREES TO BE REMOVED						
TOTAL INCHES T	60					
TOTAL 1:1 REPLA	15					
TOTAL DISEASE	0					
TOTAL REPLACE	15					

### TOTAL INCHES REPLACED - PROPOSED

LAKE MINNETONKA OHWL 929.40

### 3255 GARFIELD AVE. S. #100 MINNEAPOLIS, MN 55408

T 612 345 4275

TRAVIS VAN LIERE STUDIO

LANDSCAPE ARCHITECTURE


### WALD / ELEY RETREAT

1205 TONKAWA ROAD, ORONO, MINNESOTA 55356

The designs shown and described herein including all technical drawings, graphics and specifications thereof, are proprietary and cannot be copied, duplicated or commercially exploited, in whole or in part, without the express written permission of Travis Van Liere Studio, LLC. These are available for limited review and evaluation by clients, consultants, contractors, government agencies, and vendors only in accordance with this notice.

© Copyright 2025 Travis Van Liere Studio, LLC. All rights reserved.

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Landscape Architect under the laws of the State of Minnesota.



# EXISTING CONDITIONS AND REMOVALS PLAN

Drawn By: 2/13/2025 1/16" = 1'-0"

L011B

CONTOUR NUMBER	AREA OF CUT (FT <sup>2</sup> )	AREA OF FILL (FT <sup>2</sup> )	VOLUME CUT (FT <sup>3</sup> )	VOLUME FILL (FT <sup>3</sup> )	VOLUME CUT (YD3)	VOLUME I
931.50	518	4214	259	2107	10	7
931.00	1799	2075	1799	2075	67	7
930	3182	19	3182	19	118	,
TOTAL	5499	6308	5240	4201	194	15

### II F

- 1. SEE SHEET L000 FOR PROJECT INFORMATION, SHEET INDEX, AND LEGEND.
- 2. SEE SHEET L001 FOR GENERAL NOTES.

GENERAL NOTES

- 3. REFER TO ARCHITECTURAL DRAWINGS FOR BUILDING INFO.
- 4. ELECTRICAL CONTRACTOR, MECHANICAL CONTRACTOR, AND IRRIGATION CONTRACTOR TO COORDINATE WITH PAVING, CONCRETE, AND WALL CONTRACTORS ON SLEEVE LOCATIONS UNDER DRIVEWAYS, WALKS, AND WALLS.
- 5. REFER TO SHEET L010 EXISTING CONDITIONS PLAN FOR BOUNDARY INFORMATION. ALL CONSTRUCTION STAKING MUST BE PERFORMED BY A REGISTERED LAND SURVEYOR.
- **6.** DO NOT SCALE THE DRAWINGS. WRITTEN DIMENSIONS ARE TO BE USED FOR ALL LAYOUT WORK.
- 7. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE LANDSCAPE ARCHITECT OF ANY LAYOUT DISCREPANCIES.
- 8. ALL SITE ELEMENTS SHALL BE STAKED IN THE FIELD AND APPROVED BY
- LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION.

  9 AUTOCAD FILE AVAILABLE TO CONTRACTOR UPON REQUEST FOR FIELD
- 9. AUTOCAD FILE AVAILABLE TO CONTRACTOR UPON REQUEST FOR FIELD LAYOUT.

### KEYNOTES

- 1. EXISTING SIGNIFICANT TREE(S) TYP. SAVE AND PROTECT
- 2. EXISTING NEIGHBORING PROPERTY/SITE FEATURE SAVE AND PROTECT
- 3. EXISTING CITY STREET/ALLEY SAVE AND PROTECT, REPAIR ANY DAMAGED AREAS PER CITY STANDARDS
- 4. EXISTING SHORELINE EDGE SAVE AND PROTECT
- 5. LAKE MINNETONKA OHWL 929.40 SAVE AND PROTECT
- 6. EXISTING 100 YEAR FLOODPLAIN LINE 931.50
- 7. SANITARY SEWER LINE SAVE AND PROTECT, V.I.F.8. EXISTING WETLAND SAVE AND PROTECT
- 9. EXISTING RIP RAP SAVE AND PROTECT
- 10. EXISTING BEACH SAVE AND PROTECT

### SHEET NOTES

- BUILDING OVERHANG
   PROPOSED DOCK LOCATION, BY OWNER
- 3. EXISTING BOATHOUSE TO BE RECONSTRUCTED
- 4. DRAIN TILE
- 5. EXISTING UTILITY. SAVE AND PROTECT6. PROPOSED 100 YEAR FLOODPLAIN LINE 931.50

### WALD / ELEY RETREAT

TRAVIS VAN LIERE STUDIO

LANDSCAPE ARCHITECTURE

3255 GARFIELD AVE. S. #100

MINNEAPOLIS, MN 55408

T 612 345 4275

1205 TONKAWA ROAD, ORONO, MINNESOTA 55356


The designs shown and described herein including all technical drawings, graphics and specifications thereof, are proprietary and cannot be copied, duplicated or commercially exploited, in whole or in part, without the express written permission of Travis Van Liere Studio, LLC. These are available for limited review and evaluation by clients, consultants, contractors, government agencies, and vendors only in accordance with this notice.

© Copyright 2025 Travis Van Liere Studio, LLC. All rights reserved.

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Landscape Architect under the laws of the State of Minnesota.

TRAVIS VAN LIER

KEY PLAN
NOT TO SCALE




Rev#	Issue/Revision	Date
•	PRELIMINARY PRICING SET	08/01/2024
	ISSUED FOR PERMIT	08/14/2024
1	WATERSHED PERMIT REVISIONS	09/18/2024
2	WATERSHED PERMIT REVISIONS	10/01/2024
3	CITY DEMO REVISIONS	10/04/2024
4	CITY PERMIT UPDATES	11/18/2024
	ISSUED FOR BID	01/29/2025
	ISSUED FOR FLOOD ALT. PERMIT	2/13/2025

Drawing:
GRADING AND DRAINAGE PLAN

A.E. te: 2/13/2025 ale: 1/16" = 1'-0"

L201B



NOTE: SILT FENCE SHALL FOLLOW MNDOT SPEC. SECTION 3886.

### FIGURE 1: TYPICAL INSTALLATION FOR SILT FENCE

SILT FENCE INSTALLATION

### TABLE 1: MAXIMUM SLOPE LENGTH AND SLOPE FOR WHICH SILT FENCE IS APPLICABLE BY ACCEPTED DESIGN BY CALCULATION BY CALCULATION PRACTICES SILT FENCE STORAGE EQUALS 2 FT SILT FENCE STORAGE EQUALS MAXIMUM SLOPE FOR A 2-YEAR EVENT OR 3 FT FOR A 2 FT FOR A 100-YEAR EVENT LENGTH 100-YEAR EVENT 100:1 400 FT 900 FT 100 FT 50:1 450 FT 75 FT 200 FT 2% 100 FT 225 FT 75 FT 25:1 4% 80 FT 180 FT 20:1 75-50 5% 67 FT 150 FT 50 FT 17:1 6% 12.5:1 50 FT 50 FT 112 FT 8% 40 FT 90 FT 50-25 FT 10:1 10% 20 FT 45 FT 25-15 FT 5:1 20% 16 FT 36 FT 15 FT 4:1 25% 12 FT 27 FT 15 FT 3:1 33% 8 FT 18 FT 15 FT 2:1 50%

DESIGN

RECOMMENDATIONS

HILL) AND

THE ENDS.

FENCE.

RUNOFF.

3. MAKE THE FENCE

STABLE FOR THE

10-YEAR PEAK STORM

TO BE STORED BEHIND

4. WHERE ALL RUNOFF IS

THE SILT FENCE,

**ENSURE THAT THE** 

FENCE DOES NOT

SPECIFICATIONS

SHOWN IN TABLE

EXCEED THE

LENGTH BEHIND THE

MAXIMUM SLOPE

2. ENSURE THAT THE

SILT FENCES SHOULD

TO UP AND DOWN A

BE INSTALLED ON THE

CONTOUR (AS OPPOSED

CONSTRUCTED SO THAT

FLOW CANNOT BYPASS

DRAINAGE AREA IS NO

GREATER THAN 1/4

ACRE PER 100 FT OF

EXTEND MATERIAL ABOUT 40" ON TOP OF THE GROUND AND RANDOMLY **INSERT STAPLES** THROUGH THE MATERIAL ABOUT 20" APART STAPLES AT 3' O.C. STAPLES MUST BE INSERTED THROUGH OVERLAP MATERIAL TRANSVERSE SEAMS: **BLANKET MATERIAL MUST** OVERLAP AT LEAST 6" AND STAPLES INSERTED THROUGH BOTH FABRICS AT A MAXIMUM SPACING OF 20" APART LONGITUDINAL SEAMS: BLANKET MATERIAL MUST OVERLAP AT LEAST 6" AND STAPLES INSERTED

1. EROSION CONTROL BLANKET TO BE CATEGORY 4-COCONUT 2S FOR SLOPES GREATER THAN 5:1 AND SIDES AND BOTTOM OF ALL DRAINAGE SWALES AND PONDING AREAS AND CATEGORY 2-STRAW 2S FOR ALL SLOPES LESS THAN 5:1 PER MNDOT SPEC. SECTION 3885. 2. INSTALL PER MNDOT SPEC. SECTION 2575

AT END OF SLOPE SECURE BLANKET


20" APART THROUGH THE FABRIC

MATERIAL BY INSERTINGSTAPLES ABOUT

THROUGH BOTH FABRICS AT A

MAXIMUM SPACING OF 40" APART

## EROSION CONTROL BLANKET INSTALLATION



 BEFORE INSTALLATION APPLY TOPSOIL, FERTILIZER AND SEED TO SURFACE. 2. BEGIN AT THE TOP OF THE CHANNEL, INSTALL MATS BY ANCHORING IN A 6" DEEP BY 6" WIDE TRENCH WITH APPROXIMATELY 12" OF MAT EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR WITH A ROW OF STAPLES APPROXIMATELY 12" APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" PORTION OF MAT BACK OVER SEED AND SOIL. SECURE MATS WITH A WITH A ROW OF STAPLES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE MATS.

3. ROLL CENTER MATS IN DIRECTION OF WATER FLOW IN BOTTOM OF CHANNEL.

4. PLACE CONSECUTIVE AND ADJACENT MATS END OVER END (SHINGLE STYLE) WITH A MINIMUM 6" OVERLAP. USE A DOUBLE ROW OF STAPLES STAGGERED 4" APART AND 4" ON CENTER TO SECURE OVERLAPPED MATS.

5. FULL LENGTH EDGE OF MATS AT TOP OF SIDE SLOPES MUST BE ANCHORED WITH A ROW OF STAPLES APPROXIMATELY 12" APART IN A 6" DEEP BY 6" WIDE TRENCH


6. THE TERMINAL END OF MATS MUST BE ANCHORED WITH A ROW OF STAPLES APPROXIMATELY 12" APART IN A 6"

DEEP BY 6" WIDE TRENCH.

7. BACKFILL AND SEED AFTER STAPLING.

8. FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR PROPER INSTALLATION.

### REROSION CONTROL MAT INSTALLATION



GRAVEL CONSTRUCTION ENTRANCE DETAIL

### GENERAL EROSION AND SEDIMENT CONTROL NOTES:

SEE THE EROSION AND SEDIMENT CONTROL PLAN (L011) (WHEN UNDER ONE (1) ACRE DISTURBED) SHEETS FOR BMP CONSTRUCTION LAYOUT(S), DETAILS, AND ADDITIONAL NOTES. THE CONTRACTOR SHALL INSTALL PERIMETER EROSION CONTROL AT THE LOCATIONS SHOWN ON THE PLANS PRIOR TO

COMMENCEMENT OF ANY LAND DISTURBANCE AND/OR CONSTRUCTIONACTIVITIES. SILT FENCE AND/OR BIOROLLS SHALL FOLLOW EXISTING CONTOURS AS CLOSELY AS FEASIBLE.

BEFORE BEGINNING CONSTRUCTION, THE CONTRACTOR SHALL INSTALL A TEMPORARY CONSTRUCTION EXIT AT EACH POINT WHERE VEHICLES WILL EXIT THE CONSTRUCTION SITE. 3.1. FOR ROCK CONSTRUCTION EXITS, USE TWO (2") INCH OR GREATER DIAMETER ROCK IN A LAYER AT LEAST SIX (6")

INCHES THICK ACROSS THE ENTIRE WIDTH OF THE CONSTRUCTION EXIT. EXTEND THE CONSTRUCTION EXIT AT LEAST 50 FEET INTO THE CONSTRUCTION ZONE USING A GEO-TEXTILE FABRIC BENEATH THE AGGREGATE TO PREVENT MIGRATION OF SOIL INTO THE ROCK FROM BELOW. SEE SEDIMENT AND EROSION CONTROL PLAN SHEETS FOR BMP CONSTRUCTION DETAILS AND NOTES.

THE [GENERAL] CONTRACTOR SHALL DENOTE ON THE PLANS THE TEMPORARY PARKING AND STORAGE AREAS, WHICH SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AND CLEANING AREAS, EMPLOYEE PARKING AREA(S), AND AREAS FOR LOCATION OF PORTABLE FACILITIES, OFFICE TRAILERS, TOILET FACILITIES, ETC.

THE CONTRACTOR SHALL REMOVE ALL SOILS AND SEDIMENTS TRACKED OR OTHERWISE DEPOSITED ONTO PUBLIC AND PRIVATE PAVEMENT AREAS. REMOVAL SHALL AT LEAST BE ON A DAILY BASIS WHEN TRACKING OCCURS AND/OR WHEN NEEDED. SWEEPING SHALL BE MAINTAINED THROUGHOUT THE DURATION OF THE CONSTRUCTION AND DONE IN A

MANNER TO PREVENT DUST BEING BLOWN TOWARD ADJACENT PROPERTIES AND/OR PUBLIC RIGHT-OF-WAY (ROW). THE CONTRACTOR SHALL INSTALL INLET PROTECTION AT ALL PUBLIC AND PRIVATE CATCH BASIN INLETS, WHICH RECEIVE RUNOFF FROM ANY OF THE DISTURBED AREAS. THE CONTRACTOR SHALL CLEAN, REMOVE SEDIMENT, AND/OR REPLACE STORM DRAIN INLET PROTECTION DEVICES ON A ROUTINE BASIS SUCH THAT THE DEVICES ARE FULLY FUNCTIONAL FOR THE NEXT RAIN EVENT.

6.1. SEDIMENT DEPOSITED IN AND/OR PLUGGING THE DRAINAGE SYSTEM(S) SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND LEGALLY DISPOSED.

6.2. HAY BALES OR FILTER FABRIC WRAPPED GRATES ARE NOT ALLOWED FOR INLET PROTECTION.

6.3. SILT FENCE OR FABRIC PLACED UNDER THE GRATE IS NOT AN APPROVED FORM OF INLET PROTECTION 7. THE CONTRACTOR SHALL LOCATE SOIL OR DIRT STOCKPILES NO LESS THAN 25 FEET FROM ANY PUBLIC OR PRIVATE ROADWAY OR DRAINAGE CHANNEL. IF REMAINING FOR MORE THAN 48 HOURS, STABILIZE THE STOCKPILES BY MULCHING, VEGETATIVE COVER, TARPS, AND/OR OTHER MEANS. CONTROL EROSION FROM ALL STOCKPILES BY PLACING SILT BARRIERS AROUND THE PILES. TEMPORARY STOCKPILES LOCATED ON PAVED SURFACES MUST BE NO LESS THAN TWO (2') FEET FROM THE DRAINAGE/GUTTER LINE AND SHALL BE COVERED IF LEFT MORE THAN 24 HOURS.

THE CONTRACTOR SHALL MAINTAIN ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES IN PLACE UNTIL THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED AND ACCEPTED. INSPECT TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES ON A DAILY BASIS AND REPLACE DETERIORATED, DAMAGED, OR ROTTED EROSION CONTROL DEVICES

THE CONTRACTOR SHALL TEMPORARILY AND/OR PERMANENTLY STABILIZE ALL CONSTRUCTION AREAS WHICH HAVE UNDERGONE FINAL GRADING, AND ALL AREAS IN WHICH GRADING AND/OR SITE BUILDING CONSTRUCTION OPERATIONS ARE NOT ACTIVELY UNDERWAY AGAINST EROSION DUE TO RAIN. WIND. AND/OR RUNNING WATER WITHIN SEVEN [7]

9.1. APPROPRIATE MnDOT SEEDING MIXTURES SHALL BE UTILIZED, UNLESS OTHERWISE NOTED.

9.2. USE SEED AND MULCH, EROSION CONTROL MATTING, AND/OR SODDING AND STAKING IN GREEN SPACE AREAS. 9.3. ANY USE OF EROSION CONTROL BLANKET MUST BE FULLY BIODEGRADABLE WITH LOOSE-WEAVE NETTING (OR NETLESS). 9.4. REMOVE ALL TEMPORARY SYNTHETIC, STRUCTURAL, NON-BIODEGRADABLE EROSION AND SEDIMENT CONTROL

DEVICES AFTER THE SITE HAS UNDERGONE FINAL STABILIZATION WITH PERMANENT VEGETATION ESTABLISHMENT. 9.5. FINAL STABILIZATION FOR PURPOSES OF THIS REMOVAL IS AT LEAST 75 PERCENT ESTABLISHED COVER OVER ALL DENUDED, DISTURBED, ETC. AREAS.

ALL EXPOSED SOIL AREAS SHALL BE STABILIZED PRIOR TO THE ONSET OF WINTER CONDITIONS. ANY WORK STILL BEING PERFORMED WILL BE SNOW MULCHED AND/OR SNOW BLANKETED WITH SNOW SEEDING.

10.1. APPROPRIATE MnDOT SEEDING MIXTURES SHALL BE UTILIZED, UNLESS OTHERWISE NOTED. 11. READY MIXED CONCRETE AND CONCRETE BATCH/MIX PLANTS ARE PROHIBITED WITHIN THE PUBLIC RIGHT-OF-WAY (ROW). ALL CONCRETE RELATED PRODUCTION, CLEANING, AND MIXING ACTIVITIES SHALL BE DONE IN THE DESIGNATED

CONCRETE MIXING/WASHOUT LOCATIONS AS DETERMINED BY THE [GENERAL] CONTRACTOR. 11.1. UNDER NO CIRCUMSTANCES MAY WASHOUT WATER DRAIN INTO THE PUBLIC RIGHT-OF-WAY (ROW) AND/OR INTO ANY PUBLIC AND/OR PRIVATE STORM DRAIN CONVEYANCE.

DUE TO THE GRADE CHANGES DURING THE DEVELOPMENT OF THE PROJECT, THE CONTRACTOR SHALL BE

RESPONSIBLE FOR ADJUSTING THE EROSION AND SEDIMENT CONTROL MEASURES TO PREVENT EROSION. 13. CHANGES TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN (WHEN UNDER ONE (1) ACRE DISTURBED) OR THE STORMWATER POLLUTION PREVENTION PLANS (SWPPP) SHEETS MUST BE APPROVED, IN WRITING, BY THE EROSION

CONTROL INSPECTOR PRIOR TO IMPLEMENTATION. 13.1. THE CONTRACTOR SHALL PROVIDE INSTALLATION INSTRUCTIONS, DETAILS, ETC. FOR ALL PROPOSED ALTERNATE TYPE DEVICES.

ALL CONSTRUCTION AREAS SHALL BE PROTECTED AT THE END OF EACH WORKING DAY, THIS INCLUDES, BUT NOT LIMITED TO: BACKFILLING OF AND/OR PROTECTING TRENCHES FOR UTILITY CONSTRUCTION; PLACEMENT OF GRAVEL OR BITUMINOUS PAVING FOR ROADWAY REPLACEMENT: CLOSING AND LOCKING GATES AND/OR OPENINGS IN

TEMPORARY FENCING. ADJACENT STREETS, SIDEWALKS/TRAILS, AND/OR ALLEYS MUST BE SWEPT TO KEEP THEM FREE OF SEDIMENT, DEBRIS,

16. CONTRACTOR MUST MONITOR CONDITIONS AND SWEEP AS NEEDED OR WITHIN 24 HOURS OF NOTICE BY THE CITY/COUNTY, THE ENGINEER, OR THE OWNER.

WALD / ELEY RETREAT

TRAVIS VAN LIERE STUDIO

LANDSCAPE ARCHITECTURE

3255 GARFIELD AVE. S. #100

MINNEAPOLIS, MN 55408


T 612 345 4275

1205 TONKAWA ROAD, ORONO, MINNESOTA 55356

The designs shown and described herein including all technical drawings, graphics and specifications thereof, are proprietary and cannot be copied, duplicated or commercially exploited, in whole or in part, without the express written permission of Travis Van Liere Studio, LLC. These are available for limited review and evaluation by clients, consultants, contractors, government agencies, and vendors only in accordance with this notice.

© Copyright 2025 Travis Van Liere Studio, LLC. All rights reserved.

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Landscape Architect under the laws of the State of Minnesota.



NOTES:

1. ALL TREE PROTECTION FENCING AND EROSION CONTROL FENCING SHALL BE INSTALLED ACCORDING TO THE PLANS PRIOR TO ANY DEMOLITION. AFTER DEMOLITION OR AS NECESSARY, TREE PROTECTION FENCING MAY BE RELOCATED WITH APPROVAL FROM THE LANDSCAPE ARCHITECT. ALL TREE PROTECTION FENCING AND EROSION CONTROL DEVICES SHALL BE MAINTAINED FOR THE DURATION OF THE CONSTRUCTION PERIOD. 2. TREE PROTECTION FENCING SHALL CONSIST OF TEMPORARY METAL WIRE CHAIN LINK MESH FENCING OR APPROVED EQUAL.

CONTRACTOR SHALL NOT STORE ANY MATERIALS OR PARK ANY VEHICLES IN TREE PROTECTION ZONES. THE FENCE SHALL PREVENT TRAFFIC MOVEMENT AND THE PLACEMENT OF TEMPORARY FACILITIES, EQUIPMENT, STOCKPILES AND SUPPLIES FROM HARMING VEGETATION WITHIN THE LIMITS OF PROTECTION.

THE CONTRACTOR SHALL CLEANLY CUT ALL ROOTS EXPOSED BY GRADING AS DIRECTED BY THE LANDSCAPE ARCHITECT.

5. THE CONTRACTOR SHALL USE DESIGNATED CONSTRUCTION ENTRANCES AND STAGING AREAS.

TREE PROTECTION FENCING INSTALLATION

INSTALL SHREDDED HARDWOOD MULCH (MNDOT TYPE 6). EQUIVALENT MATERIAL MAY BE SUBSTITUTED AT THE DISCRETION COIR LOG 6"-7" MINIMUM DIAMETER OF THE ENGINEER. STAKE DRIVEN THROUGH LOG MESH


10' MIN LENGTH

-0.5"X0.5" OPENING IN NET

WEDGE OR 2"X2" STAKE

PRE-DRILLED HOLES

BIOLOG INSTALLATION



Rev # Issue/Revision
PRELIMINARY PRICING SET 08/01/2024 ISSUED FOR PERMIT 08/14/2024 WATERSHED PERMIT REVISIONS 09/18/2024 WATERSHED PERMIT REVISIONS 10/01/2024 CITY DEMO REVISIONS 10/04/2024 CITY PERMIT UPDATES 11/18/2024 ISSUED FOR BID 01/29/2025 ISSUED FOR FLOOD ALT. PERMIT 2/13/2025

EROSION CONTROL AND TREE PROTECTION DETAILS

Drawn By

2/13/2025

L601

SCALE: N/A